BRUHATH BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of Work : PROVIDING SANITARY PIPELINES AT MISSING BITS IN WARD NO.12 IN SHETTYHALLI SUB DIVISION

Sl. No.	Sanctioned Qty	Description of Work	Unit	Sanctioned Rate (in Rs)	Amount
1	973.66	Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications. in hard soil.	Cum	299.98	292078.53
2	540.00	Providing and laying in position to required level or slope of internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints,including cost of materials, labour charges complete as per specifications.	M	554.38	299365.20
3	540.00	Providing and laying in position plain cement concrete M7.5 using 40mm and down size graded granite metal, machine mixed concrete laid in layers not exceeding 15 cms thick, well compacted, for internal diameter stoneware pipes including cost of materials, labour charges, HOM curing complete as per specifications – 230mm	M	493.96	266738.40

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahangara Palike,
Dasarahalli Division, Bengaluru-57

Scanned by CamScanner

Sl. No.	Sanctioned Qty	Description of Work	Unit	Sanctioned Rate (in Rs)	Amount
4	19.00	Constructing brick masonry circular type manhole 0.91m internal dia at bottom and 0.56m dia at top with table moulded onmodular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and downsize granite metal and making necessary channel in cement concrete M 50 with 20mm and downsize granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diametre confirming IS :12592, total weight cover and frame to be not less than 182 kg, fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM complete as per specifications. (Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid separately) deep 1.67m	No	22392.50	425457.50
5	973.66	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications.	Cum	134.62	131074.11

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahangara Palike,
Dasarahalli Division, Bengaluru-57

Scanned by CamScanner